

DATE OF ISSUE:
December 29, 2015

DEPARTMENT OF GENERAL SERVICES
BUREAU OF PROFESSIONAL SELECTIONS AND ADMINISTRATIVE SERVICES
18TH AND HERR STREETS
HARRISBURG, PENNSYLVANIA

BULLETIN NO. 4

on

**PROJECT NO. DGS 404-62, PHASE 1 – REVISED REBID
RENOVATIONS AND EXPANSION OF TIPPIN GYMNASIUM, CLARION UNIVERSITY, CLARION, CLARION
COUNTY, CLARION PA
DLA/GUND PARTNERSHIP JOINT VENTURE, FOSTER PLAZA 9, SUITE 200, 750 HOLIDAY DRIVE,
PITTSBURGH, PENNSYLVANIA 15220**

**PROPOSAL SUBMISSION DATE – TUESDAY, JANUARY 12, 2016 – 2:00PM EST
SUBCONTRACTORS QUALIFICATION STATEMENTS DUE – THURSDAY, JANUARY 14, 2016 – CLOSE OF
BUSINESS**

ALL CONTRACTS

- Item 1 Per specification section 01010-2 states that the (.1) contractor owns slabs on grade per the Summary of Work. Per specification section 01310-20, Paragraph 1.10 I states that the (.1) contractor owns sealing of trenches after piping and conduits are installed and applies to new and/or existing conditions.
- Item 2 The (.2) Contractor disconnects the steam and condensate piping in the existing steam tunnel and the (.1) contractor removes the piping and the tunnel.
- Item 3 Page 01310 – 11, HVAC Construction Sequence 1B, Item 2032:
Delete: Replace existing steam entry into Tippin, including pressure reducing station.
Add: Replace existing steam entry into Tippin, not including pressure reducing station.

SPECIFICATION CHANGES – CONTRACT NO. DGS 404-62, PHASE 1.1

- Item 1 At 133416-3, 2.5 DECK SYSTEM, paragraph A.:
Delete: Decking Systems Extrusions: 6063-T6 aluminum alloy, mill finish.
Add: Decking Systems Extrusions: 6063-T6 aluminum alloy, factory blasted and then anodized.

SPECIFICATION CHANGES – CONTRACT NO. DGS 404-62, PHASE 1.3

- Item 1 Page 21 0500-3, Part 2.02, paragraph B:
Delete: Steel Pipe: _____, black.
1. Steel Fittings: _____
Add: Steel Pipe: Black steel pipe ASTM A53, sprinkler mains 2 1/2" and larger Schedule 10 rolled grooved and joined by grooved couplings. Branch lines 2" and smaller Schedule 40 threaded and joined by 125# class cast iron fittings.
1. Steel Fittings: ASME A53.

Item 2 Page 22 10 05 – 3, Section 2.05, Paragraph A. Copper Tube:
Add: Type "L" piping can be substituted for type "K".

DRAWING CHANGES – CONTRACT NO. DGS 404-62, PHASE 1.1

Item 1 At drawing 1/A0.24, change the quantity of rows for Telescoping Stands #1 and #2 from ten (10) to eleven (11). The seating quantities shown on the seating manifest are correct.

Item 2 At drawing 4/A3.32, change the dimension for the telescoping stands from "11TREADS AT 2'-0"=22'-0" to "10 TREADS AT 2'-0"=20'-0".

DRAWING CHANGES – CONTRACT NO. DGS 404-62, PHASE 1.2

Item 1 At drawing 2/H0.13, all miscellaneous steel supports, anchor plates, brackets, and bolted/welded connections for steam piping to be furnished and installed by the (.2) Contractor.

Item 2 At drawing C-H0.11 between manholes 14 and 14A, provide detail 'C' on H0.12 to reroute steam piping around the new storm line installation.

DRAWING CHANGES – CONTRACT NO. DGS 404-62, PHASE 1.3

Item 1 At drawing P1.14, sinks tagged as S-1 & S-3 shown in the rooms 339A and 345 are furnished by the Using Agency and installed by the (.3) Contractor.



Gary R. Taylor, P.E. Director
BUREAU OF ENGINEERING AND ARCHITECTURE

Call the Professional's Office, Telephone No. at (412) 921-4300, for names of those who have secured plans and specifications.

PLEASE ACKNOWLEDGE RECEIPT OF EMAIL WITHIN 24 HOURS BY COMPLETING THE BOTTOM OF THE PAGE AND EMAIL TO DLA/GUND PARTNERSHIP AT cjshaw@DLAplus.com

NAME

TITLE

DATE

FIRM