

DATE: August 2, 2018

DEPARTMENT OF GENERAL SERVICES
BUREAU OF PRE-CONSTRUCTION
1800 HERR STREETS
HARRISBURG, PENNSYLVANIA

ADDENDUM NO. 2

on

PROJECT NO. DGS A-0377-0001 PHASE 000

PROJECT TITLE - SCI Forest - Complete Construction of Building 6 Correctional Industries Plant

PROFESSIONAL:

Corrections

1920 Technology Parkway

Mechanicsburg, PA, 17050

If you submitted a bid through e-Builder prior to this Addendum being issued, your bid has been discarded and you must re-submit your bid(s) through e-Builder prior to the bid opening date and time. Please see Section 4.C. of the Instruction to Bidder

GENERAL CHANGES – ALL CONTRACTS

Item 1 - Any notes on addendum cover sheets which direct proposers to submit bids through e-Builder should be disregarded. Proposals should be submitted in accordance with the procedures outlined within the RFP.

Item 2 - Proposers are reminded that time is of the essence. Project Phasing, in accordance with SECTION 112 of the Project Procedures Manual for Retained Professionals in Design Build Contracts, will need to be employed, as required, to meet the project completion dates identified within item 4-1.H.9 of the RFP.

Item 3 - Pre-Installation Meetings, in accordance with SECTION 905.6 of the Project Procedures Manual for Retained Professionals in Design Build Contracts, will be required for Earthmoving, Excavation, Paving, Slab Construction, Under-Slab Construction, Foundations and Booth Installation.

Item 4 - Delete reference to Specification Section 01030 within Appendix C - Cost Submission Form. This Specification Section does not exist as there is only one base bid for the project.

Item 5 - RFP Part 4 - Work Statement item 4-1.C listing of Record Drawings has been revised to include drawings A3.27, A6.08 and A6.09.

Item 6 - RFP Part 4 - Work Statement item 4-1.F has been revised to provide clarification for Flammable Storage Area requirements as follows, "CONTRACTOR shall furnish and install UL Listed storage compartments for the storage of flammable liquids and aerosols. Total volume of flammables is anticipated to exceed 10 gallons, and be less than 120 gallons. CONTRACTOR shall perform necessary modifications to accommodate the code compliant placement of storage compartment within the designated area."

Item 7 - RFP Part 4 - Work Statement item 4-1.F has been revised to provide clarification for Exterior Overhead Door requirements as follows, "New exterior overhead doors must be sized to accommodate the safe passage of plow trucks with mounted snow-plows and wing plows. Penn Dot plow truck with mounted front and side-wing plow measures 11'H x10'6"W. Existing structural columns are spaced 23 feet apart. Doors shall be sized as not to require modification of existing structural members. For the Purposes of the bid. Figure on 16'Wx 14'H minimum door opening.

Item 8 - RFP Part 4 - Work Statement item 4-1.F.2 has been revised to read as follows, "Plant-Specific Equipment to be Client Agency Furnished and Contractor installed under the scope of this project are as detailed in the included literature under Appendix N3. Listing of the equipment is as follows:"

Item 9 - RFP Part 4 - Work Statement item 4-1.F.2.a.i has been revised to read as follows, "To be relocated BY CONTRACTOR from a temporary installation location prior to substantial completion of Building Six."

Item 10 - RFP Part 4 - Work Statement item 4-1.F.2.b has been added as follows, "Four Wall Mounted Fume Extractors with two hoses each."

Item 11 - RFP Part 4 - Work Statement item 4-1.F.2.b.i has been added as follows, "Contractor to provide

mounting system which allows movement of fume extractor as needed within the welding area.”

Item 12 - RFP Part 4 - Work Statement item 4-1.F.3.n has been revised to read as follows, "Rough-in, wiring and final connections for Client Agency furnished Security Cameras, locking devices and overhead door position indicators. For the Purposes of the bid figure on six security cameras.

Item 13 - RFP Part 4 - Proposers are directed to refer to Work Statement item F.3.b.i for clarification on designated floor areas on the plans.

Item 14 - RFP Part 4 - Proposers are directed to refer to Appendix N.4 in the Drawing Folder for summary of available capacities of Hot Water, Chilled Water and Power from existing plant which serve Building 6.

Item 15 - RFP Part 4 - Work Statement item 4-1.F.4 has been added as follows:

Plant specific equipment to be Client Agency Furnished and Client Agency installed. Equipment detailed in the included literature under Appendix N3 and indicated on drawing A-1. Listing of the equipment for which supporting infrastructure will be required is as follows:

- a. Four Heavy Duty Machine Wired Mobile Column Lifts (no optional cross beams).
- b. Rough Terrain Vertical Masted Forklift.
- c. Rough Terrain Material Handler.
- d. One 14 inch "roll-in" vertical tilt-frame cut-off band saw
- e. One Industrial Ironworker
- f. One 13 ft x 3/8" Hydraulic Shear
- g. One 330 Ton x 13ft Hydraulic Pressbrake
- h. One Drill Press
- i. One Milling Machine.
- j. Five plasma cutters
- k. Five oxygen/acetylene welders.

SPECIFICATION CHANGES – ALL CONTRACTS

Item 1 - No Change - Refer to specification section 16100 for DOC safety and security requirements and protocols, including tool inventory control.

Item 2 - No Change - Refer to General Conditions for general jobsite safety requirements. OSHA Requirements apply to all work performed on site.

DRAWING CHANGES – ALL CONTRACTS

Item 1 - See revised drawings previously included in Appendix N2 which now include all layers: M2.07, M2.07H, M2.08, M2.08H.

Item 2 - See drawings A2.08, A2.09, A6.08, A6.09, A3.15, A3.27 now included as part of Appendix N2 for pertinent architectural plans and details.