

DATE OF ISSUE:  
March 22, 2016

DEPARTMENT OF GENERAL SERVICES  
BUREAU OF PROFESSIONAL SELECTIONS & ADMINISTRATIVE SERVICES  
18<sup>TH</sup> AND HERR STREETS  
HARRISBURG, PENNSYLVANIA

BULLETIN NO. 1

On

PROJECT NO. D.G.S. 948-78 PHASE 2  
REWIRE PUMPKIN BALL LIGHTS  
THE CAPITOL COMPLEX  
HARRISBURG, DAUPHIN COUNTY, PENNSYLVANIA  
WEIGAND ASSOCIATES, INC., 4201 EAST PARK CIRCLE, SUITE 103, HARRISBURG, PA

BID DATE: April 5, 2016  
BID OPENING TIME: 2:00 P.M.

Subcontractors' Qualification Statements due Thursday, April 7, 2016 at Close of business.

GENERAL CHANGES – CONTRACT NO. DGS 948-78 PHASE 2

Item 1 - CLARIFICATION: This project includes only a Base Bid #1. Please refer to revised Appendix D, attached to this document.

SPECIFICATION CHANGES – CONTRACT NO. DGS 948-78 PHASE 4.2

Item 1 - REVISE: Section 01120.1.8.B to read as follows: "Photographs must be captured by a single lens reflex type digital camera using a CCD or CMOS imaging sensor and capable of producing images sixteen (16) megapixels or greater."

Item 2 - CLARIFICATION: The reference to the CREE lamp was a typographical error and should be removed. Provide the Philips lamp as specified in 16515.2.2.A.

DRAWING CHANGES – CONTRACT NO. DGS 948-78 PHASE 4.2

Item 1 - REMOVE: General Note #13, in its entirety, from sheet E0.01.

Item 2 - CLARIFICATION: Refer to specifications for specific requirements associated with Architectural Conservationist.

Item 3 - CLARIFICATION: General Note #22, sheet E0.01, is intended to advise the contractor that some fixtures may have been field modified and not previously documented. Modifications may include additional lamp sockets and exposed wiring within the fixture. The contractor shall only rewire and provide lamp sockets to return the fixture to the original design. The contractor shall be responsible for assuring that all wiring is properly concealed with a cover when the work is complete.

Item 4 - CLARIFICATION: Lamp counts within lighting fixture schedule, Sheet E0.01, indicate the total number of lamps required for each fixture. See Item 3 above for further explanation.

Item 5 - CLARIFICATION: Floor plans indicate electrical circuits for reference purposes only. Replacement of branch circuit wiring is not within the scope of this project.

Item 6 - ADD: Sheet E3.01, attached to this document, to the drawing set.



---

GARY R. TAYLOR, P.E., DIRECTOR  
BUREAU OF ENGINEERING AND ARCHITECTURE

Call the Professional's Office,  
Telephone No. (717) 561-6800, for  
names of those who have secured plans and specifications.

PLEASE ACKNOWLEDGE RECEIPT OF FAX WITHIN 24 HOURS BY COMPLETING BOTTOM OF  
PAGE AND FAX TO (717) 561-6801.

---

NAME

TITLE

DATE

---

FIRM

## APPENDIX D

## 948-78.4 COST SUBMISSION FORM

**Submit 1 original in a sealed envelope separate from the Technical Submission and the DBE Submission**

In conformity with the plans and specifications prepared by the Professional and after examination of the site and all contract documents, which are made a part hereof as if fully set forth herein, the undersigned submits this cost submission. Enclosed is a bid guaranty in an amount not less than 10% of the highest base bid. Proposer understands this bond will be forfeited if this Proposal or any part hereof is accepted by DGS and the Proposer fails to furnish approved Contract Bond or execute the contract. Proposer hereby agrees to execute the Standard Form of Agreement and furnish the Contract Bond, on the form incorporated in the contract documents, in the amount of 100% of the contract price within ten (10) days after receipt of the contract from DGS. It is understood that if work is not completed within the time period set forth in the Notice to Proposers, or any such extension of that time, the Contractor shall pay DGS as liquidated damages and not as a penalty for such failure, the amount of Two hundred, seventy dollars (\$270.00) per day for each and every calendar day thereafter until such work is completed and accepted.

**FOR AN EXPLANATION OF BASE BIDS, SEE SECTION 01030 OF THE SPECIFICATIONS**

**Base Bid #1:**

Lump Sum Offer: \_\_\_\_\_ dollars and \_\_\_\_\_ cents  
(Written)  
\$ \_\_\_\_\_  
(Figures)

Proposer acknowledges receipt of the following Bulletin(s) and agrees they are part of this Bid Proposal:

Bulletin # \_\_\_\_\_ Issue Date \_\_\_\_\_      Bulletin # \_\_\_\_\_ Issue Date \_\_\_\_\_

Bulletin # \_\_\_\_\_ Issue Date \_\_\_\_\_      Bulletin # \_\_\_\_\_ Issue Date \_\_\_\_\_

Bulletin # \_\_\_\_\_ Issue Date \_\_\_\_\_      Bulletin # \_\_\_\_\_ Issue Date \_\_\_\_\_

**PROPOSER IS A CONTRACTOR/INDIVIDUAL:**

Witness:

\_\_\_\_\_

By:

\_\_\_\_\_

Contractor / Individual

**PROPOSER IS A PARTNERSHIP OR LIMITED LIABILITY COMPANY (LLC):**

Witness:

\_\_\_\_\_

By:

\_\_\_\_\_

General Partner / Authorized LLC Member

**PROPOSER IS A CORPORATION:**

Attest: By:

\_\_\_\_\_

Secretary

\_\_\_\_\_

President

**PROPOSER IS A JOINT VENTURE:**

Attest: By:

\_\_\_\_\_

Secretary

\_\_\_\_\_

President

Attest:

\_\_\_\_\_

Secretary

\_\_\_\_\_

President

PROJECT NORTH	PA-SPCS NORTH




PUMPKIN LIGHT FIXTURE  
- FIXTURE TYPE "L"  
SCALE: 1/8" = 1'-0"



SMALL GLOBE LIGHT FIXTURE  
- FIXTURE TYPE "C"  
SCALE: 1/8" = 1'-0"



SUSPENDED PUMPKIN LIGHT  
WITHOUT UPPER LIGHT  
- FIXTURE TYPE "K"  
SCALE: 1/8" = 1'-0"



SUSPENDED PUMPKIN LIGHT  
WITH UPPER LIGHT  
- FIXTURE TYPE "D"  
SCALE: 1/8" = 1'-0"



PENDANT LANTERN  
- FIXTURE TYPE "A"  
SCALE: 1/8" = 1'-0"



WALL MOUNTED PUMPKIN  
LIGHT FIXTURE  
- FIXTURE TYPE "M"  
SCALE: 1/8" = 1'-0"




STATUE MOUNTED GLOBE  
LIGHT FIXTURE  
- FIXTURE TYPE "G"  
SCALE: 1/8" = 1'-0"



STANCHION LIGHT FIXTURE WITH  
4 SURROUNDING GLOBES  
- FIXTURE TYPE "J"  
SCALE: 1/8" = 1'-0"



STANCHION LIGHT FIXTURE WITH  
8 SURROUNDING GLOBES  
- FIXTURE TYPES "B" & "B1"  
SCALE: 1/8" = 1'-0"



RAIL POST GLOBE LIGHT FIXTURE  
WITH 4 SURROUNDING GLOBES  
- FIXTURE TYPE "H"  
SCALE: 1/8" = 1'-0"



PILLAR LIGHT FIXTURE WITH  
8 SURROUNDING GLOBES  
- FIXTURE TYPE "R"  
SCALE: 1/8" = 1'-0"

- MEANING GENERAL NOTES - COMMON TO ALL FIXTURES:**
- THE EXHIBIT WORK AREA IS ESSENTIALLY A MUSEUM QUALITY SPACE AND THE USHERY FIXTURES ARE HISTORIC. ALL WORK IS TO BE PERFORMED PER THE EXISTING PRESERVATION CONTRACT REQUIREMENTS UNDER THE SUPERVISION OF THE CONTRACTOR'S HISTORIC PRESERVATIONIST. SEE SPECIFICATIONS FOR ADDITIONAL INFORMATION.
  - THE CONTRACTOR SHALL PERFORM THE REQUIRED WORK USING THE APPROPRIATE MEANS AND METHODS TO PREVENT DAMAGE TO THE SURFACES ADJACENT TO THE FIXTURE, PARTICULARLY SURFACES IN CONTACT WITH THE FIXTURE COMPONENTS.
  - DOCUMENT THE EXISTING CONDITIONS PRIOR TO AND DURING THE FIXTURE DISASSEMBLY PROCESS.
  - DISASSEMBLE THE FIXTURES ONLY TO THE EXTENT REQUIRED TO PERFORM THE WORK.
  - REMOVE AND RETRACE ALL LINE VOLTAGE WIRING TO THE FIXTURE AND BACK TO THE BRANCH-WIRE JUNCTION BOX. PROVIDE FIXTURE WIRE PER UL 64, NEC ARTICLE 402, AND PER THE SPECIFICATIONS. INSTALL REPLACEMENT WIRING VIA THE SAME PATHWAYS AS EXISTING.
  - CERTAIN FIXTURES HAVE BEEN PREVIOUSLY RETROFITTED WITH FINE ALUMINUM NOTIFICATION DEVICES AND LOW VOLTAGE WIRING; THESE ARE EXISTING TO REMAIN.
  - REMOVE ALL EXISTING LAMPS.
  - REMOVE AND REPLACE ALL EXISTING LAMP HOLDERS. SOME FIXTURES HAVE BEEN MODDED OVER TIME TO ADD ADDITIONAL LAMPS AND LAMP HOLDERS; THESE ARE UNDOCUMENTED. THE CONTRACTOR SHALL REMOVE IN THE BID COSTS FOR 30 ADDITIONAL LAMP HOLDERS AND ASSOCIATED WIRING TO REPLACE THE EXISTING LAMP HOLDERS ON A ONE FOR ONE BASIS. GREATLY EXCEED THE QUANTITY OF LAMPS AS SCHEDULED ON THE FIXTURE SCHEDULE. IF A FIXTURE HAS BEEN MODDED AND HAS FEWER LAMP HOLDERS THAN THE SCHEDULED QUANTITY, ADVISE THE ENGINEER OF THE CONCRETE AND UPON RECEIPT OF NOTIFICATION TO PROCEED PERFORM THE SCHEDULED QUANTITY OF LAMP HOLDERS IN THE SAME MANNER AS OTHER FIXTURES OF THIS TYPE.
  - INSPECT THE INTERIOR OF THE FIXTURES FOR DAMAGED SUPPORTS AND ANCHORS (FROM WIRING, LAMP HOLDERS, CRISTAL GLOBES AND GLASS, AND FIXTURE COMPONENTS). OBTAIN FABRICATE REPLACEMENT SUPPORTS AND ANCHORS AND MAKE REPAIRS TO PROPERLY SECURE AND ANCHOR THE SUBJECT ITEMS AT LEAST EQUIVALENT TO THE APPROVED ORIGINAL DESIGN AND AS REQUIRED FOR CODE COMPLIANCE.
  - CLEAN THE INTERIOR OF THE FIXTURE BEFORE REASSEMBLY.
  - REASSEMBLE THE FIXTURE AND CLEAN THE ENTIRE EXTERIOR OF THE FIXTURE.
  - SEE SPECIFICATIONS FOR ADDITIONAL REQUIREMENTS.

16	20
17	18
13	15
12	14
11	12
09	08
07	06
05	04
03	02
01	01
TEL	DESCRIPTION

AS-BUILT REVISIONS

		Date
--	--	------

**WAP** WAP Consulting Engineers  
**WIGAND ASSOCIATES, INC.**  
 1000 PENNSYLVANIA AVENUE, SUITE 1000  
 HARRISBURG, PENNSYLVANIA 17101-2000

COMMONWEALTH OF PENNSYLVANIA  
 DEPARTMENT OF GENERAL SERVICES  
 HARRISBURG, PENNSYLVANIA  
 PROJECT No. DGS 948-78, Phase 2

<b>VERIFY SCALE</b> BAR IS ONE (1) INCH LONG ON ORIGINAL DRAWING: 0 1 IF BAR IS NOT ONE (1) INCH LONG, ADJUST SCALE ACCORDINGLY.	<b>REWIRED PUMPKIN BALL LIGHTS THE CAPITOL COMPLEX</b> HARRISBURG, DAUPHIN COUNTY, PENNSYLVANIA
CONTRACTOR SHALL FIELD VERIFY ALL DIMENSIONS. VARIANCE FROM CONTRACT DOCUMENTS NOT PERMITTED WITHOUT BUREAU OF ENGINEERING AND ARCHITECTURE APPROVAL.	<b>LIGHTING FIXTURE DETAILS</b> DRAWN BY: CEB DATE: 02.18.2016 DRAWING NUMBER: E3.01 CHECKED BY: MAW SCALE: AS NOTED