

DATE: December 1, 2023

DEPARTMENT OF GENERAL SERVICES  
BUREAU OF CAPITAL PROJECT DESIGN MANAGEMENT  
1800 HERR STREET  
HARRISBURG, PENNSYLVANIA

**ADDENDUM NO. 8**

on

**PROJECT NO. DGS C-0373-0009 PHASE 001**

**PROJECT TITLE - SCI Mahanoy - Repairs/Renovations to Switchgear & Generators**

**PROFESSIONAL:**

HF Lenz Company  
1407 Scalp Ave  
Johnstown, PA, 15904

**If you submitted a bid prior to this Addendum being issued, your bid has been discarded and you must re-submit your bid(s) prior to the bid opening date and time.**

GENERAL CHANGES – ALL CONTRACTS

Item 1 - Sheet P-001 - Revise all references to ".2 contractor" to be ".3 contractor".

Item 2 - Refer to Sheet H-402 & H-403 for backdraft damper locations. Dimensions may be scaled from drawings based on basis of design generator. Size may vary depending on actual generator submitted.

Item 3 - Refer to sheet notes on H-series drawings: The .1 contractor shall provide and install louvers, motor actuator on louvers and filter rack on louvers, refer to specifications section 089100 - Louvers. The .2 contractor shall provide the filter racks and the 2" thick pleated filters, refer to specifications section 234100 - Particulate Air Filtration.

Item 4 - Refer to specifications section 234100 - section 3.3. Installation of filters paragraph D indicates the following: Do not operate fan system until filters (temporary or permanent) are in place. Replace temporary filters used during construction and testing with new, clean filters at the time of turnover and section 3.5 Cleaning indicates the following: After completing system installation and testing, adjusting, and balancing of air-handling and air-distribution systems, clean filter housings and install new filter media.

Item 5 - Refer to specifications section 233850 - Stationary Engine Exhaust Venting Systems for exhaust vent material.

Item 6 - Sheet HD-401 - Revise note #5: "Disconnect and remove existing fuel oil day tank and associated piping, vents, wiring, hangers, supports, etc. in its entirety (including removal of approximately 200 gallons of fuel each tank). Patch roof opening to match existing by .1 contractor."

Item 7 - Sheet HD-401 - Revise note #11: "Disconnect and remove existing remote genset radiator and associated piping, hangers, exterior steel support, etc. in its entirety (including removal of approximately 500 gallons of anti-freeze each radiator)."

Item 8 - Refer to sheet notes on Drawing H-501, .1 contractor is responsible for new housekeeping pads, refer to Drawing H-501.

Item 9 - HVAC drawings do not indicate existing traps to be removed or new traps to be installed.

Item 10 - Refer to Building 14 Section "A" on Drawing H403, structural supports by .1 contractor, refer to structural drawings (typical).

Item 11 - The .1 contractor is responsible for painting of beams, steel, metal walls. Any painting required in Division 21 & Division 23 specifications shall be by the .2 & .3 contractors respectively.

SPECIFICATION CHANGES – ALL CONTRACTS

Item 1 -

DRAWING CHANGES – ALL CONTRACTS

Item 1 -