

DATE: January 31, 2023

DEPARTMENT OF GENERAL SERVICES
BUREAU OF CAPITAL PROJECT DESIGN MANAGEMENT
1800 HERR STREETS
HARRISBURG, PENNSYLVANIA

ADDENDUM NO. 18

on

PROJECT NO. DGS C-0210-0004 PHASE 001

PROJECT TITLE - PA State Police Greensburg - DNA Laboratory Facility New Building

PROFESSIONAL:

DRS Architects, Inc.
One gateway Center
Pittsburgh, PA, 15222

If you submitted a bid prior to this Addendum being issued, your bid has been discarded and you must re-submit your bid(s) prior to the bid opening date and time.

GENERAL CHANGES – ALL CONTRACTS

Item 1 - The Proposal Submission Deadline is now scheduled for February 28, 2023 at 2:00pm.

Item 2 - The cut off for questions submitted in e-Builder was CoB 11/11/22, and no further questions will be answered following this addendum.

SPECIFICATION CHANGES – ALL CONTRACTS

Item 1 - N/A

DRAWING CHANGES – ALL CONTRACTS

Item 1 - N/A

RFI RESPONSES - ALL CONTRACTS

Question 01.26.2023 01:07 PM Eastern Time: Detail 1 & 4 on page A541 show both spray foam insulation and an air barrier to be installed. Since the spray foam insulation alone achieves the air/vapor barrier, can you please confirm the air barrier is not necessary. Detail 5 on A325 shows the continuous air barrier from the roof to wrap over the parapet wall and intersect with spray foam insulation. Can you please confirm that the roofer owns this.

Response: For Detail 1 and 4 on Sheet A541, the spray foam alone is sufficient to act as the air/vapor barrier. No additional air/vapor barrier is needed under the spray foam, except at transitions to other materials or insulation. For Detail 5 on Sheet A325, the air/vapor barrier needs to wrap over the parapet as shown, and transition under the spray foam for about 8". It is the responsibility of the .1 contractor to determine which sub-contractor will perform the work.